



Shared components: Web server By-me

R01945

Smart systems&products / By-me Plus / Shared components / DIN devices

Web server By-me

Spare web server for local and remote supervision of the By-me home automation system via IP, installation on DIN rail (60715 TH35), occupies 8 modules size 17.5 mm

Product Status

2 - Will be discontinued

Minimum order quantity

1 NR

Sheets, Manuals, Documentation

- [Multilanguage instructions sheet \(1270 kb\)](#)
- [Manuale installatore \(6830 kb\)](#)
- [Manuel installateur \(6928 kb\)](#)
- [Manual del instalador \(7014 kb\)](#)
- [Manual del instalador \(6694 kb\)](#)
- [Εγχειρίδιο τεχνικού εγκατάστασης \(7022 kb\)](#)
- [Installationsanleitung \(7049 kb\)](#)
- [Manuale utente \(13412 kb\)](#)
- [User manual \(12949 kb\)](#)
- [Manual de usuario \(14787 kb\)](#)
- [Εγχειρίδιο χρήστη \(14187 kb\)](#)
- [Bedienungsanleitung \(13848 kb\)](#)
- [By-me automation-fw Compatibility \(206 kb\)](#)



Product Software

- [FW_IPWebServer_By-me_REL-02.11.000.25172_20230427.zip](#)

Video

- [Customising the Web Server](#)


Technical data

- **Class group:** Installation bus systems
- **Class:** System interface/media gateway for bus system
- **Bus system KNX:** No
- **Bus system KNX-RF (Radio Frequent):** No
- **Other bus systems:** Other
- **Radio frequent bidirectional:** No
- **Model:** LAN-systems interface
- **Mounting method:** DRA (DIN-rail adapter)
- **Width in number of modular spacings:** 8
- **Demounting protection:** No
- **With LED indication:** Yes
- **Updateable:** No
- **Protocol:** Other
- **Provider dependent:** No
- **Visualization:** No
- **Web-Server:** Yes
- **Radio interface:** No
- **IR interface:** No
- **Degree of protection (IP):** IP20

Certifications

- 00. CE Marking - EU
- 43. UKCA mark - Great Britain
- 99. WEEE Directive ([download](#))

Packaging



Code 8007352615922
Quantity 1 NR
Dim. 22x15.9x8.2 [cm]
Weight 1,880.832 [g]

Legal

Vimar reserves the right to change at any time and without notice the characteristics of the products reported. Installation should be carried out by qualified staff in compliance with the current regulations regarding the installation of electrical equipment in the country where the products are installed. For the terms of use of the information on the product info sheet see [Conditions of Use](#).